



NOTES:

1. REDUCED PRESSURE BACKFLOW PREVENTER SHALL MEET THE APPROVAL OF THE FOUNDATION FOR CROSS CONNECTION CONTROL AND RESEARCH.
2. FOR CERTIFIED TESTS REQUIRED, SEE DISTRICT REQUIREMENTS.
3. WATER SERVICE WILL NOT BE TURNED ON UNLESS DISTRICT HAS RECEIVED A SATISFACTORY CERTIFIED TEST REPORT AND THE INSULATION MEETS ALL OTHER DISTRICT REQUIREMENTS.
4. IF UNINTERRUPTABLE SERVICE IS REQUIRED, A DUAL R.P.V. ASSEMBLY TO BE INSTALLED.
5. 3" INSTALLATIONS AND ABOVE SHALL BE DUCTILE IRON PIPE.

	NO.	REV. DATE	BY	<h2>REDUCED PRESSURE BACKFLOW PREVENTER</h2>		
	1	OCT. 1992	JO			
	2	APR. 1994	JO	APPROVED BY  01/2015 DATE		
	3	JAN. 1998	BEC			STANDARD PLAN
	4	DEC. 2003	BEC			
5	DEC. 2014	KSB	MANAGER			